BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41730

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

Name of Work:Providing Recharging Pits to Existing Borewell Points Ward No 11 Kuvempunagara Vidyaranyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of KARIYALLAPPA ( )	
				In Figures	In Words
1	83.63	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	500.12	Rupees Five Hundred and Twelve Paise Only
2	63	Laying Reinforced cement concrete pipe NP4 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications. MORTH Specification No. 2900 B. 1200 mm dia etc complete as per specifications and directions of engineer in charge of the work	m	9140.64	Rupees Nine Thousand One Hundred Forty and Sixty Four Paise Only
3	7.42	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. etc complete as per specifications and directions of engineer in charge of the work	Cum	2188.53	Rupees Two Thousand One Hundred Eighty Eight and Fifty Three Paise Only
4	116.29	0734 - Providing Aggregate 53 mm nominal size etc complete as per specifications and directions of engineer in charge of the work	Cum	896.15	Rupees Eight Hundred Ninety Six and Fifteen Paise Only
5	7.42	0750 - Providing Aggregate 40 mm nominal size etc complete as per specifications and directions of engineer in charge of the work	Cum	927.72	Rupees Nine Hundred Twenty Seven and Seventy Two Paise Only
6	7.42	0749 - Providing Aggregate 20 mm nominal size etc complete as per specifications and directions of engineer in charge of the work	Cum	927.72	Rupees Nine Hundred Twenty Seven and Seventy Two Paise Only
7	4.95	0334 - Providing sand / Artifical Sand / Manufactured sand etc complete as per specifications and directions of engineer in charge of the work	Cum	1352.72	Rupees One Thousand Three Hundred Fifty Two and Seventy Two Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92